



OAHS 321 John Street

June 17, 2026

PV01 Addendum

Subject:	Scope Clarification for Base Building & Solar Contractor (in Cash Allowance)
Prepared by:	Jordan Hoogendam, P.Eng. p. 1-888-338-6363 x701 e. jordan@zonengineering.com
Project Address:	321 John Street Cobourg ON
Owner:	Ontario Aboriginal Housing Services (OAHS)
Owner Representative:	LGA Architects

Item	Description
1.01	<u>Solar PV – Base Building Electrical Demarcation</u> The scope of work delineation has been added to the E3 Drawing by Kirkland Engineering Ltd., and the PV-201 Drawing by Zon Engineering Inc. For clarity the demarcation point is on the load side of the Exterior Disconnect Switch. The 600A Unfused Disconnect, feeders/conduits between disconnect and Panelboard DP-1 including 600A (550AT) breaker in the panelboard shall be supplied and installed by the Base Building Electrical Contractor. All solar equipment downstream from the 600A Unfused Exterior Disconnects shall be covered under the Solar PV Cash Allowance.

Attachments:

PV-101 – Roof Plan Drawing
PV-201 – Single Line Drawing

End of Document